

Prefabricated Utility Cupboard

SAFER

BETTER

BETTER

FASTER

OGREENER

MANUFACTURE

Typically saves
75% of overall
build time
compared to
traditional
methods

Developed for the residential and modular housing market, NG Bailey's PUC solution:

- **O** Provides **programme** certainty
- **Reduces multi-trade working** and on-site congestion
- O Delivers a **factory-quality and fully tested product** to exact client specifications.

The ideal packaged solution, each unit is designed bespoke to project requirements with the key principle to minimise utility cupboard types and simplify the overall build.

Each PUC houses the mechanical and electrical equipment for the home, including HIU, CIU, MVHR, Consumer Units, and UFH Manifolds, alongside associated pipework, containment, and cabling.

Constructed from a choice of steel and fitted with bespoke melamine panelling (colour choices available for both), the units can be upgraded to be fully furnished: including floor, ceiling panels, worktops, light fittings etc.


To deliver a quality product and maintain consistent output, our offsite factory has designated PUC assembly lines that adopt tried and tested manufacturing methods. The way we build, brings efficiencies that support our clients' needs.

Every unit is delivered with its own comprehensive quality check record.

With 20+ years delivering offsite modular products, we design and manufacture both 2D (panelised) and 3D units.



Prefabricated Utility Cupboard



- 1. Heat Interface Unit (HIU)
- 2. Mechanical Ventilation Heat Recovery Unit (MVHR)
- 3. Underfloor Heating Manifold (UFH Manifold)
- 4. Consumer Unit
- 5. Adjustable Feet
- 6. Primary Heating Flow and Return
- 7. Secondary Heating Flow and Return
- 8. Incoming Cold Water Services
- 9. Outgoing Cold Water Services
- 10. Cold Feed to HIU
- 11. Outgoing Hot Water Services
- 12. Ductwork to MVHR
- 13. Ceiling Panels
- 14. Containment Feeding CU and Housing Electric Faceplates
- 15. Worktop
- 16. Space for Washing Machine
- 17. Access Panel to Stack
- 18. Waste for W/M Trap, MVHR Condensate and HIV Blow Off
- 19. Double Check Valve
- 20. W/M Valve
- 21. Tenant Valve/Water Meter
- 22. Tundish for Blow Off
- 23. W/M Socket
- 24. Fused Spurs
- 25. Double socket
- 26. Three Pole Isolator
- 27. Waterless Trap
- 28. MVHR Condensate
- 29. HIV Blow Off Pipework
- 30. Fixing for Castors



Scan here

for more information



